

Name of Work : Works for enhancing the facilities in the Hospital community kitchen
QUOTATION SHEDULE

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		
1	2	3	4	5	6	7
1	24.991 sqm	11.41.2 Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4(1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete.Size of Tile 600 x 600 mm.	sqm			
2	14.152 sqm	11.48.2 Grouting the joints of flooring tiles having joints of 3 mm width, using epoxy grout mix 0.70 kg of organic coated filler of desired shade (0.10 kg of hardener and 0.20 kg of resin per kg). including filling /grouting and finishing complete as per direction of Engineer-in-charge.Size of Tile 600x600 mm	sqm			

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		
1	2	3	4	5	6	7
3	1.057 cum	50.6.1.7 Solid block masonry using pre cast solid blocks (Factory made) of size 40x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for foundation and plinth with thickness 15 cm in : CM 1:6 (1 cement : 6 coarse sand) etc complete	cum			
4	14.943 sqm	13.1.2 12 mm cement plaster of mix:1:6 (1 cement : 6 fine sand)	sqm			
5	0.346 cum	5.3 Reinforced cement concrete work in beams, suspended floors, roofs, having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (Zone III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources).	cum			
6	4.896 sqm	5.9.3 Centering and shuttering including strutting, etc. and removal of form for: Suspended floors, roofs, landings, balconies and access platform	sqm			

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		
1	2	3	4	5	6	7
7	1.000 each	17.10.2.1 Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required: Kitchen sink without drain board 610x510 mm bowl depth 200 mm	each			
8	1.000 each	18.18.3 Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete: 25 mm nominal bore	each			
9	1.000 each	18.15.2 Providing and fixing brass bib cock of approved quality : 20 mm nominal bore	each			
10	15.000 meter	50.18.7.3.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer- in- Charge 25 mm dia 12 Kgf/cm ² - Internal work - Exposed on wall	meter			

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quantity	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		
1	2	3	4	5	6	7
11	3.000 meter	50.18.7.6.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fittings with one step PVC solventcement and testing of joints complete as per direction of Engineer-in-Charge 50 mm dia 10 Kfg/cm - Internal work- Exposed on wall	meter			
12	25.920 kg	5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars of grade Fe-500D or more	kg			
13	28.446 sqm	13.48.1 Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications:Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of special primer applied @ 0.75 ltr /10 sqm	sqm			
					GRAND TOTAL	

CONTRACTOR

CHIEF EXECUTIVE OFFICER

Item no	Quanti ty	Description of work	Unit	Quoted rate		Amount
				In figure	In words	Rs.
				Rs.		
1	2	3	4	5	6	7

CONTRACTOR

CHIEF EXECUTIVE OFFICER